



okeanospoolsgta.com | (647) 234-7694 | joe@okeanosontario.com

What to Expect

Your Pool Installation Timeline

Pre-Construction Phase (2–6 Weeks)

Before any ground is broken, there's planning to do:

- Discovery call and site visit — we assess your property
- Pre-site consultation — pool model selection, placement, options
- Contract signing and deposit
- Permit application (if required by your municipality)
- Scheduling excavation and installation dates

This phase typically takes 2–6 weeks depending on permit processing times in your municipality.

Week 1 — Contract & Planning

- Okeanos confirms pool model, equipment, and delivery schedule
- Utility locates completed (Ontario One Call)
- Homeowner clears access path and removes fencing/obstacles

Week 2 — Excavation

- Excavation crew arrives — full dig to pool depth
- Soil loaded into bins and hauled away
- Base preparation: geotextile + 4" clear stone foundation

Duration: typically 1 day

Installation Day

- Pool shell delivered on 53' truck
- 45-ton crane lifts pool into excavated hole
- Pool levelled and positioned (tolerance: within 1cm)
- Backfilling with ½" clear stone
- Plumbing connected — pool to equipment pad
- Equipment placed, drainage well installed

Duration: typically 1–2 days



okeanospoolsgta.com | (647) 234-7694 | joe@okeanosontario.com

After Installation

- You fill the pool immediately + install sump pump
- You arrange electrical and gas connections
- You install fencing and update insurance

Equipment Startup & Pool School

- Okeanos returns once electrical/gas is connected
- Equipment startup and verification
- Pool School: hands-on training for your family

Total timeline: approximately 4–8 weeks from first call to swimming (including permits).

**Timeline varies based on permits, weather, scheduling, and site conditions.*